SHIMOGA DIVISION.

Dated 26th June 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 16th July 1928, for constructing a Local Fund Dispensary building with inpatient wards, etc., at Anavatti, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates both in words and figures at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 650 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Local Fund Dispensary Building with inpatient wards, etc., at Anavatti, Sorab Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate for constructing Local Fund Dispensary at Anavatti, Sorab Taluk, Shimoga District.

No.	Items of work	Per	Quantity			
			Dispensary and Inpatient ward	Kitchen attached to dispensary	Latrine	Dead House
1	Earthwork excavation for foundation and filling in basement.	Cyd.	119	4	4	18
2	Stone jelly in chunam concrete ...	C.ft.	1186	...	...	160
3	Burnt size stone in clay filling in foundation	„	1582	...	...	...
4	Burnt size stone in mortar	„	1103	175	118	363
5	Burnt brick in mortar	„	3745	283	159	276
6	Burnt stone slabs 5" to 6" thick, roughly dressed and fixed.	S.ft.	176	13	...	48
7	Burnt stone slabs 5" to 6" thick, nicely dressed and fixed.	„	160	..	...	42
8	Teakwood doors half panelled and half glazed with iron bars complete, with glazed ventilators at top frame ($3\frac{1}{2}$' x 5').	„	308	...	...	...
9	Teakwood battened door with hinges, etc., complete.	„	...	18	...	...
10	Teakwood panelled door with hinges, etc., complete.	„	...	...	...	16
11	Teakwood rectangular ventilators with iron bars and glazed shutters in bath rooms.	„	16	...	...	...
12	Teakwood windows with shutters on one side only in 4 halves top glazed and bottom panelled with iron bars complete rectangular glazed ventilators above.	„	342	...	...	...
13	Teakwood battened windows with four half shutters and iron bars, etc, complete.	„	...	5	...	...

514

No.	Items of work	Per	Quantity			
			Dispensary and Inpatient ward	Kitchen attached to dispensary	Latrine	Dead House
14	Teakwood windows half panelled and half glazed with iron bars complete.	S ft.	...	...	...	18
15	Teakwood circular ventilator with glazed shutters	,,	21	...	...	...
16	Teakwood panelled shutter with frames for wall shelves.	,,	95	...	...	...
17	Teakwood planks 1" thick for shelves ...	,,	44	...	...	...
18	Teakwood pillars 7" square with base and capital 8' long including painting.	No.	8	...	...	...
19	Pointing with cement mortar	Sqr.	4·40	0·45	...	0·63
20	Plastering with chunam	,,	80·14	5·28	4·34	6·92
21	Honey comb work with white-washing 2 coats.	,,	...	...	...	2·40
22	Teakwood work wrought and put up with wood oiling and tarring portion resting on wall.	C.ft.	138·6	10·21	...	24·0
23	Teakwood ornamental eave board 9" wide with painting.	R.ft.	313	...	...	...
24	Teakwood finials big	Each	3	...	...	...
25	Teakwood pendant	,,	13	...	...	...
26	Teakwood finial small	,,	1	...	...	...
27	Roofing with First Class Mangalore tiles on teak reepers.	Sqr.	28·30	2·21	...	3·74
28	Ridge tiles set in cement mortar ...	R.ft.	153	15¼	...	...
29	Ventilating tiles	Each	...	...	...	2
30	Flooring with Mangalore 9" square tiles on 3" concrete with cement pointing.	Sqr.	9·22	...	...	...
31	Flooring with Kadapa slabs on 3" concrete with cement pointing.	,,	5·81	·70	·62	...
32	White and colour washing 2 coats ...	,,	80·14	5·28	4·34	6·92
33	Painting 2 coats	,,	5·90	...	...	...
34	Chocolate painting 2 coats	,,	...	·45	...	...
35	Binding walls at gable ends 1' x 9" with brick in chunam and chunam plastering	R.ft.	72	28	...	...
36	Ornamental chunam plastering work round the two front windows, etc.	L. S.	Rs.	...	...	...
37	Providing sinks in bath examining and compounding rooms.	Each	4	...	...	...
38	Teakwood screen with doorway including wood oiling, etc., as per design.	C.ft.	98	...	...	...
39	Wooden counter with necessary iron brackets on both sides for delivery of medicines, etc.	L. S.	Rs.	...	...	...
40	Plain zinc sheets with ½" teakwood planking underneath including wood oiling and cement mortar band.	S.ft.	227	...	...	...
41	Inscription of name in gable	L. S.	Rs.	...	...	...
42	Levelling site, etc	,,	,,	...	...	...
43	Drainage works	,,	,,	...	...	...
44	Burnt brick in mortar arch work around circular ventilators.	C.ft.	49	...	...	...
45	Fixing date stone	L. S.	Rs.	...	...	...
46	Providing mortar and pestle	,,	...	Rs.	...	...
47	Wood oiling	Sqr.	9·71	...	...	...
48	Providing smoke tiles	Each	...	4	...	...
49	Burnt brick in mortar, coping around with plastering.	R.ft.	...	...	41	...
50	Tarring, providing seats and clearing site ...	L. S.	...	...	Rs.	...
51	Constructing cistern providing buckets and cast iron out-let pipe, etc.	,,	...	...	,,	...
62	Stone flagging with cement pointing 3" to 4" thick slabs.	S ft.	...	...	...	150

M. A. SRINIVASACHARI,
Executive Engineer,
6 D